



ASSAM ELECTRICITY GRID CORPORATION LIMITED

OFFICE OF THE MANAGING DIRECTOR

Regd. Office: (FIRST FLOOR), BIJULEE BHAWAN, PALTANBAZAR; GUWAHATI - 781001

CIN: U40101AS2003SGC007238GSTIN: 18AAFCA4973J9Z3

PHONE: 0361-2739520 Web: www.aegcl.co.in



No. AEGCL/MD/Tech-765/AIIMS/2018/SS&TL/ 15

Dtd: 03.02.2020

CORRIGENDUM AND TIME EXTENSION - II

IFB No. : AEGCL/MD/Tech-765/AIIMS/2018/SS&TL/IFB

Bid Identification No. AEGCL/MD/Tech-765/AIIMS/2018/SS&TL/BID

- The following may be noted regarding submission of EMD along with the bid in the e-tender portal:
 - Bidders willing to submit their EMDs in Hard copy in BG format may note that When the website shows a prompt regarding "EMD through BG/ST or EMD Exemption Allowed - Yes or No", they are to reply "Yes" and then proceed to the next page. They shall have to submit a scanned copy of the BG document in the next page of the portal.
 - However, the Tender Fees has to be submitted online compulsorily and No exemption is allowed.
 - AEGCL's account details to be for preparation of the Hard copy EMD BG are as follows:
 NAME: ASSAM ELECTRICITY GRID CORPORATION LIMITED
 A/C NO: 10566984188
 IFSC: SBIN000221
 MICR CODE: 781002003
 BRANCH ADDRESS: NEW GUWAHATI BRANCH (00221)
- In addition to the above, the bid identified against the above referred IFB and Bid identification no. is amended to the following extent -

In the BoQ uploaded online, following may be noted:

- BoQ3 - Schedule No 1B: SCHEDULE OF QUANTITY (FOUNDATION, ERECTION, TESTING AND COMMISSIONING - SS):**

The text in item sl. nos., as listed below, is amended to be read as follows:

SL No	Item Description	Qty	Units
1.01	Erection , testing and commissioning of 25 MVA, 132/33 kV, 3-Ph, YNyn0, Z =10 %, ONAN/ONAF with copper wound Power Transformer with OLTC (+5% to -15% in steps of 1.25%), RTCC panel including laying & terminating of LT power and control cables as required. The Transformer shall be suitable for single / Single ACSR Zebra Conductor termination on HV and Single ACSR Zebra conductor on LV side. The transformer shall be supplied with Bushing mounted CTs for WTI/OTI & REF protection. Ratios shall be as per SLD. The Transformer shall be suitable for outdoor installation & complete with all accessories to meet the technical specification.	1	Nos
1.02	Construction of Transformer pad for above including supply of all foundation materials & Labour as per drawing furnished with the bid document	1	Nos



ASSAM ELECTRICITY GRID CORPORATION LIMITED

OFFICE OF THE MANAGING DIRECTOR

Regd. Office: (FIRST FLOOR), BIJULEE BHAWAN, PALTANBAZAR; GUWAHATI - 781001

CIN: U40101AS2003SGC007238GSTIN: 18AAFCA4973J9Z3

PHONE: 0361-2739520 Web: www.aegcl.co.in



1.03	Erection , testing and commissioning of 250 kVA, 33/0.433 kV, Copper Wound, 3ph, Dyn-11, Z=4% outdoor type "Station Service Transformer" with OFF Circuit Tap Changer , - 5% to + 5 % in steps for 2.5 % & including 10 % spare oil including construction of foundations and supply of all foundation materials.. MV connection shall be through single ACSR Panther Conductor, LV Side shall be connected through XLPE Insulated LT cable.	2	Nos.
------	--	---	------

Due to the technical constraints in the e-tender portal, the updated BoQ (incorporating corrections) is not possible to be uploaded. However, these corrections shall be done during evaluation stage after opening of price bids. Bidders should quote rates keeping the above in mind.

3. The tender submission deadline also may be extended as follows:
Tender submission date: 12.00 hrs on 17.02.2020
Tender opening date: 14.00 hrs on 18.02.2020

All other terms and conditions shall remain same.


Chief General Manager(PP&D)
Assam Electricity Grid Corporation Ltd
Bijulee Bhawan, Paltanbazar, Guwahati – 1

Memo No : MD/AEGCL/ Tech-765/AIIMS/2018/SS&TL/ 15 (a)

dtd: 03 .02.2020

Copy to:-

1. The AGM-III, HQ,AEGCL :-for necessary action for uploading on AEGCL's website.


Chief General Manager (PP&D).