





OFFICE OF THE MANAGING DIRECTOR
Regd. Office: (FIRST FLOOR), BIJULEE BHAWAN, PALTANBAZAR; GUWAHATI - 781001

CIN: U40101AS2003SGC007238GSTIN: 18AAFCA4973J9Z3

PHONE: 0361-2739520Web: www.aegcl.co.in

No. AEGCL/MD/Tech-765/AIIMS/2018/SS&TL/ 9

Dtd: 21.01.2020

CORRIGENDUM & TIME EXTENSION - I

IFB No.: AEGCL/MD/Tech-765/AIIMS/2018/SS&TL/IFB Bid Identification No. AEGCL/MD/Tech-765/AIIMS/2018/SS&TL/BID

The bid identified against the above referred IFB and Bid identification no. is amended to the following extent -

1. Volume II: SECTION - 4 TECHNICAL SPECIFICATION FOR POWER TRANSFORMERS:

4.29.0 DATA SHEET FOR TRANSFORMERS

A new item vide SI No. 23 is added as follows:

SL. NO	DESCRIPTION	TRANSFORMER CLASS 132/33 kV
23	25 MVA Tansformer with 10% Impedance	NLL/FLL/AL (KW)
	High Load Loss	18/ 140/-
	Low Load Loss	14/ 115/-

2. Volume II: SECTION - 8 TECHNICAL SPECIFICATION OF ISOLATORS:

8.13.0. TECHNICAL DATA SHEET FOR ISOLATORS

SI. No. 6. : Short time current rating for 132kV Isolator shall be 40 kA.

- 3. In the BoQ uploaded online, following may be noted:
 - BoQ3 Schedule No 1B: SCHEDULE OF QUANTITY (FOUNDATION, ERECTION, TESTING AND COMMISSIONING - SS):

The text in Item descriptions in the SI Nos. listed below may be read as follows:

- 8 "ETC and Construction of Foundation including all foundation materials of Lattice type Structural Steel (For Column and Beam types refer substation drawing.)."
- 8.12 "Erection of equipment mounting structure of the following "



ASSAM ELECTRICITY GRID CORPORATION LIMITED





OFFICE OF THE MANAGING DIRECTOR

Regd. Office:(FIRST FLOOR), BIJULEE BHAWAN, PALTANBAZAR; GUWAHATI - 781001

CIN: U40101AS2003SGC007238GSTIN: 18AAFCA4973J9Z3

PHONE: 0361-2739520Web: www.aegcl.co.in

ii. BoQ6 - Schedule No 2B: SCHEDULE OF QUANTITY (FOUNDATION, ERECTION, TESTING AND COMMISSIONING - TL):

The gty and text in item sl. nos., as listed below, is amended to be read as follows:

SL No	Item Description	Qty	Units
3	Soil Investigation :Detailed Soil Investigation upto a depth of 7 mtr in soil and 3 Mtr in rock Strata in Normal conditions & 40 mtr in Special Locations. (All kinds of soil and rock strata)		Nos.
4	Excavation, including shoring, shuttering, dewatering, etc. upto the required depth as per foundation specification/drawings. (Fully Submerged)		cm
6.1	M - 15 grade concrete	134.16	Cum
8	Supplying, fitting and fixing in position reinforcement bars conforming to relevant I.S. Code from Primary Producer: TATA/SAIL/Esser Steel/ Jindal steel/Shyam steel/RINL, TMT Corrosion resistant steel (CRS) reiforcement bar for R.C.C. work/ R.B. walling including straightening, cleaning, cutting and bending to proper shapes and length as per details, supplying and binding with 20G annealed black wire and placing in position with proper blocks, supports, chairs, spacers etc. complete. (No extra measurement for lap, hook, chair, anchor etc. will be entertained in the measurement as they are included in the rate) (Upto 1st floor level)	12.87	МТ

Due to the technical constraints in the e-tender portal, the updated BoQ (incorporating corrections) is not possible to be uploaded. However, these corrections shall be done during evaluation stage after opening of price bids. Bidders should quote rates keeping the above in mind.

4. The tender submission deadline also may be extended as follows:

Tender submission date: 12.00 hrs on 10.02.2020 Tender opening date: 14.00 hrs on 11.02.2020

All other terms and conditions shall remain same.

Chief General Manager(PP&D)
Assam Electricity Grid Corporation Ltd

Bijulee Bhawan, Paltanbazar, Guwahati – 1

Memo No: MD/AEGCL/ Tech-765/AIIMS/2018/SS&TL/9(A)

dtd: 21.01.20

Copy to:-

1. The AGM-III, HQ, AEGCL :-for necessary action for uploading on AEGCL's website.

Chief General Manager (PP&D)