

BOQ (Package-A)

Various types of O&M works related to Transmission Line

Sl. No	Description of Work	UoM	Rate(Excl. GST)
1	Re- Jumpering of damaged/snapped jumper of the Transmission Line.		
a	For 132kV TL	No	
b	For 220kV TL	No	
2	Replacement of damaged disc insulator of Suspension point per string.		
a	For 132kV TL	Per String	
b	For 220kV TL	Per String	
3	Replacement of damaged disc insulator of Tension point per string.		
a	For 132kV TL	Per String	
b	For 220kV TL	Per String	
4	Re-stringing of snapped conductor due to disc failure or failure of conductor.		
a	For 132kV TL	Per KM	
b	For 220kV TL	Per KM	
5	Replacement of hardware fittings like vibration dampers etc.		
a	For 132kV TL	Per Job	
b	For 220kV TL	Per Job	
6	Repairing/replacement of missing tower members.	Per MT	
7	Carrying of tower materials, conductors etc by means of transport from store to site.	Per MT/KM	
8	Head loading of tower materials, conductors etc (For Hilly areas)	Per MT/Mtr	
9	Repairing/replacement of damage leg etc including all necessary civil work.	Per Leg	
10	Re-stringing of snapped Ground wire.	Per KM	
11	Attending emergency hot spot in the Transmission Line.	Per Job	
12	Jungle Cleaning in the corridor of the Line.	Per KM	
13	Emergency tree/bamboo clearing in the corridor of the line (during fault)	Per Section	
14	Temporary Protection using bamboo palisade with gunny bag fill of sands of Tower legs washout due to erosion.	Per SQMtr	
15	Repairing/Replacement of Damaged Cross Arm. (Materials will be supplied by AEGCL)		
a	Suspension Type , 132kV Level	Per Job	
b	Tension Type, 132kV Level	Per Job	
c	Suspension Type , 220kV Level	Per Job	
d	Tension Type, 220kV Level	Per Job	

16	a	Painting of Tower , Type-A +0Mtr Extn	Per Tower	
	b	Painting of Tower , Type-A +3Mtr Extn	Per 3 Mtrs	
	c	Painting of Tower , Type-A +6Mtr Extn	Per 6 Mtrs	
17	a	Painting of Tower , Type-B +0Mtr Extn	Per Tower	
	b	Painting of Tower , Type-B +3Mtr Extn	Per 3 Mtrs	
	c	Painting of Tower , Type-B +6Mtr Extn	Per 6 Mtrs	
18	a	Painting of Tower , Type-C +0Mtr Extn	Per Tower	
	b	Painting of Tower , Type-C +3Mtr Extn	Per 3 Mtrs	
	c	Painting of Tower , Type-C +6Mtr Extn	Per 6 Mtrs	
19	a	Painting of Tower , Type-D +0Mtr Extn	Per Tower	
	b	Painting of Tower , Type-D +3Mtr Extn	Per 3 Mtrs	
	c	Painting of Tower , Type-D +6Mtr Extn	Per 6 Mtrs	
20		Earthing of per tower (Including supply of all earthing materials)	Per tower	
Total Amount (Excluding GST)				

<i>Bidder Name and Address →</i>	
<i>Seal & Signature</i>	